



- NOTES**
NOT TO SCALE
- Signage to be Class 400400T reflective AS 1742.3 refer TNSW TCAWS V6.1, Section 6.
 - Signage to be placed to best suit road and sight conditions per section 6.2 TNSW TCAWS V6.1. Contradictory signage to be covered.
 - Affected residents and businesses to be notified of the proposed works schedule including changed conditions.
 - Emergency services, local bus companies, taxi services and waste management collection providers to be notified of proposed changed conditions and potential delays.
 - Private driveway and business access to be maintained at all times, or alternate arrangements provided prior to commencement of works.
 - All works crew and vehicle drivers to be briefed on TGS conditions including pedestrians, cyclists and local resident and business services.
 - Daily risk assessment to include pedestrian movements, and Pedestrian Movement to be monitored at all times.
 - Access for public to route buses to be maintained, or alternative access arrangements negotiated prior to commencement of works.
 - Work vehicles and plant to have at least one operating rotating or flashing yellow light.
 - All site traffic to adhere to normal traffic conditions. No U-Turn or Reversing on live carriage ways unless under traffic control.
 - Traffic Controllers to maintain escape route, be positioned with a minimum of 1.5D approach sight distance at all times.
 - Where signs cannot be duplicated, a second sign must be repeated at 0.5D.
 - 4 cones to be placed at spacing 4m preceding Control Positions.
 - Only persons with a current Prepare Work Zone Traffic Management Plan Card can make modifications to this plan.

Date: 06/04/2023 **Author:** Jeremy Segol TCT1015735 **Project:** SWR Running Festival
TGS: 01 Approved : David Barnes TCT1023836
Comments:
 TGS for New Entrance Road South

RECORD OF MODIFICATIONS:	
DATE MODIFIED:	_____
NAME:	_____
CERTIFICATE NO:	_____
SIGNATURE:	_____